ERS Implementation Report Card 4/21/2015

ERS Recommendation	PSE Role	City Role	Actions to Date
Current System Study (Ch. 2)	Current System Assessment Recommendations (2.	.5) SUMMARY	
Includes all preliminary recon	mendations in sections: PSE's Past and Present R	eliability and Outage Performance (2.2) Review	y of PSE's System Design (2.3) Review of PSE Work Practices (2.4)
Current System 1: Reliability Progress	PSE has several programs underway to reduce the number and duration of outages, including: • Harden the Downtown system; • Underground cable life extension/ replacement; • Replace old switches & transformers; • Address underperforming circuits; • Install reclosers & SCADA;	The City can and should proactively monitor progress and the extent of those programs focused on improved reliability of the City's power distribution system. This will require that the City add staff with power system expertise.	 PSE confirmed plan schedule & progress per ERS Report; Bellevue SAIDI/SAIFI data shows better performance than for rest of PSE service area; At this time city budget for PSE monitoring deployed for legal and technical outside experts, and a partial new FTE approved in the 2015-2016 budget for working with the WUTC—currently vacant.
	Major technology upgrade for outage and distribution management		
Current System 2a:	PSE has ongoing reliability initiatives and performs system-wide and targeted projects to	The City should track the reliability impacts experienced in the various neighborhoods.	 2013 PSE Reliability Overview – Distribution system serving Bellevue 95 distribution circuits serving Bellevue in 2013
Reliability Progress	improve system reliability	Since, in the future, PSE will be reporting additional reliability information including storm outages, the City can utilize this information to determine the effectiveness of the various reliability programs and projects, and to work with PSE in identifying circuits requiring attention. A fast track implementation of system improvements is an option for the City to explore with PSE, although accelerated investments might have a negative impact on the power rates. Track effectiveness; explore fast track implementation; meet w/PSE annually to understand projects & schedules proposed impacts on reliability	 75 circuits (79%) had performance better than our system wide average 20 circuits (21%) experienced no outages 20 circuits (21%) had SAIDI or SAIFI figures exceeding system wide average figures. 16 of these circuits have been addressed or require no corrective action. The remaining 4 circuits have improvement actions identified. 2013 PSE Reliability Overview – Downtown Performance continues to be very good Clyde Hill transformer replaced Center Substation Bank rebuilt & sealed Center circuit 25 to be rebuilt in 2015 22 other reliability projects completed 72 additional reliability projects planned

ERS Recommendation	PSE Role	City Role	Actions to Date		
Current System Study (Ch. 2) Current System Assessment Recommendations (2.5) SUMMARY					
Includes all preliminary recommendations in sections: PSE's Past and Present Reliability and Outage Performance (2.2) Review of PSE's System Design (2.3) Review of PSE Work Practices (2.4)					
Current System 2b:	There are several programs underway to	It is recommended that the City meet with	The annual reliability workshop has been held 3 times; last was		
	address outages and to reduce duration of	PSE on an annual basis to understand what	December, 2014; next meeting 2Q, 2015. PSE, City staff and		
Reliability Progress	outages.	projects are being identified and scheduled	stakeholders attend; specific tasks are directed and an annual		
		each year with the specific goal of improved	reliability report is provided and reviewed.		
		reliability. The City can monitor PSE			
		programs underway to address outages and			
		to reduce duration of outages.			
Current System 3:	Opportunities exist to advance undergrounding	The City should investigate opportunities	The City continues to implement Policy UT-39 by analyzing projects		
	of lines by inter-utility cooperation	for additional undergrounding of	using tariff schedules 73, 74, and the CIP to advance		
Undergrounding		distribution lines through coordination of	undergrounding i.e. the City examined projects on West Lake		
Opportunities		multiple utility projects and evaluation of	Sammamish Parkway and 120 th road projects but did not include		
		funding for conversion of overhead lines to	undergrounding due to high cost;		
for distribution lines		underground cable circuits by forming local	The MOU stresses a continuing and active role of the City and PSE		
		improvement districts. Further, the City	in seeking opportunities to leverage joint projects or other		
		needs to decide how to approach	opportunities for undergrounding. Recognizing that the		
		conversion of overhead distribution lines,	Comprehensive Plan already requires new distribution lines to be		
		used primarily in residential areas, to	undergrounded through Policy UT-39, and that the Franchise		
		underground systems, which requires	Agreement allows the City to require undergrounding for		
		special funding mechanisms. Investigate	relocations, the City proposed amended policies through the Comp		
		advancement of undergrounding of	Plan Update regarding funding alternatives and feasibility including		
		distribution lines through LIDs, & other means; explore conversion of overhead	encouraging LIDs by neighborhood request;		
		distribution lines & funding mechanisms			
Current System 4:	The visual review of overhead circuits indicates	The City should review its vegetation	• Current work plan item for DCD		
Current system 4.	that there are many substations and lines	policies specifically in the area of	Current work plan item for DSD		
Vogetation Management	located in heavily wooded areas and the only	substations to look at alternative			
Vegetation Management	way to significantly improve reliability is to	vegetation approaches specifically where			
	Perform more comprehensive tree trimming	the risks for large scale disturbances related			
	Terrorm more comprehensive tree trimining	to vegetation management issues is high			
		Review vegetation management policies,			
		esp. near substations			
		cop. ficul substations			

ERS Recommendation	PSE Role	City Role	Actions to Date
Current System 5:	In 2013, PSE began deploying several major	After deployment, selected City personnel	Pre-event coordination model for forecasted storms developed by
Outage Management System	system replacements, including customer information system, GIS and outage management. These deployments are part of PSE's multi-year modernization plan. These systems are integrated to provide accurate and timely information to customers in the event of disruptions – a strong interest of the City's for many years. A major benefit for emergency coordination and public outreach is the PSE Outage Map (on web and mobile app) released in 2014 that shows helpful information such as location on the map, start time, customers impacted, cause and status of response.	involved in emergency response to learn the capabilities to assist in communication to the Bellevue community. Emergency response personnel learn capabilities	 PSE and city OEM; City public information officers and PSE developed communications structure integrated with City Incident Command structure; Monthly OEM and PSE meetings with Homeland Security to advance incident preparedness results reviewed in annual reliability workshop PSE implemented three new integrated systems in April 2013 including their Customer Information System (CIM), Geospatial Information System (GIS) and Outage Management System (OMS). PSE notes that all have been successfully implemented although they are still learning how best to use full capabilities. The City continues to monitor PSE's progress on its system
Current System 6:	impacted, cause and status of response.		modernization and smart grid efforts.
Recommendations for PSE	Several key components of high system reliability	are within PSE's control.	
Current System 6a:	To achieve high reliability of the power supplied via the 115kV power transmission lines, system reinforced to handle all N-1 contingencies by adding 115kV transmission lines to the substations feeding the Downtown	Monitor; permit	• These System Plan planned facilities are included in the <i>updated</i> Utilities Element Figure UT-5a.
Current System 6b:	For substations which at present are fed from a single 115kV line, reinforce substations with a second 115kV line for N-1 contingency.	Monitor; permit	 Lake Hills—Phantom Lake 115kV: New transmission line between existing substations to provide redundant (looped) transmission connection for three substations – permitting in 2014/2015 with planned construction in 2016. City Council decision 4/20/2015.
Current System 6c:	Continue to reinforce distribution system to meet N-1 criteria for the entire city	Monitor; permit	System Plan implementation, monitored through annual meetings, Comp Plan updates, and permitting

ERS Recommendation	PSE Role	City Role	Actions to Date
Current System 6d:	 Continue implementation of system programs: hardening, distribution automation, upgrades of OMS & DMS; preventive replacement of low reliability transformer uture System Assessment Recommendations (3.4) 	Monitor; permit	Actions taken and documented through the annual reliability workshop. See Current System 2b.
			s) including Table 6 Major Project Road Map
Future System 1: Energy Efficiency Programs	PSE's long-range plans indicate significant reliance on energy efficiency for the management of the peak electric power demand	The City should lead the electric energy efficiency effort to assist PSE in reaching its peak electric power demand goals to avoid using or building new peak electric power plants. Electric energy efficiency programs require active outreach to customers and citizens to support various outreach initiatives. This is a longer-term issue that will be included in future IRPs. The City should remain active in the IRP process and should begin to understand potential long-term impacts of this strategy.	 Bellevue selected to advance to the semifinal round of the Georgetown University Energy Prize Solarize Bellevue successfully underway Adopted streamlined process for permitting small-scale solar Yearly update of city greenhouse gas inventory Leveraged \$1.2M Energy Efficiency and Conservation block grant for natural resource conservation projects Hired resource conservation manager to reduce municipal water and electric usage Created the Eastside Sustainable Business Alliance The City owns and operates 22 electric vehicle charging stations Expanded the Carbon Yeti Campaign Only local jurisdiction with staff representation on PSE IRP advisory group process—participated in last three IRPs City energy efficiency measures that have been used at recent pump station projects. The 2015-2021 CIP program includes rehabilitation of 8 water and 12 wastewater pump stations. At each of these projects the city will continue to perform energy analyses to reduce energy consumption and impacts to the grid. Through both capital and operational savings at buildings and pump stations, the city has reduced peak monthly demand from about 4,386 kW in 2011 to 4,008 kW in 2014 and reduced kWh usage from 16.7 million kWh in 2011 to 15.4 million kWh in 2014.

ERS Recommendation	PSE Role	City Role	Actions to Date
Future System 1: Energy Efficiency Programs (cont'd)			 Replacing traffic signal and street lighting with LED. LED traffic signal conversion has saved 73,000 kWh/year since 2010. LED streetlight conversions have saved 38,972 kWh since 2011 (cumulative) and in 2015 will save 1.19 million kWh/year. The city is also working much more closely with PSE on implementing commercial energy efficiency programs through the forthcoming Bellevue Urban Smart program – a downtown building district for high efficiency commercial buildings. While the focus of this program is on efficiency through behavior change by occupants in buildings, there is a strong component of facility infrastructure updates including smart metering technologies.
Future System 2: Smart Grid Initiatives	PSE is initiating Smart Grid programs to comply with WUTC requirements including: upgrade technologies; upgrade SCADA in transmission substations; Distribution SCADA on feeder breakers; extend fiber optic cable through T&D systems	The City should review the overall PSE plan and determine their level of support for the various customer initiatives that would be appropriate for the City to provide. The types of initiatives to be considered relate to customer energy management, demand response, and home automation.	 Actions taken and documented through the annual reliability workshop; in 2014 workshop for example, Utilities and PSE staff identified synergistic opportunities to apply smart meter technologies in their infrastructure operations (not customer meters) These strategies are separately carried out amidst a collaborative work and reporting strategy. A Smart Grid supporting interactivity between data and users is a key component. The City through its economic development Vision is also pursuing a Smart City strategy to include high speed data options for businesses and residents and in which a smart grid can play a key role. The city capital budget for 2015-2016 includes initial funding for broadband telecommunications rollouts relying on smart grid technology. PSE's smart grid efforts are also being phased in. Remote data acquisition devices and SCADA (supervisory control and data acquisition) switches are being deployed to gather real-time information and monitoring for more efficient operations and response. The City's Smart City effort provides an opportunity to be supportive of PSE's smart grid effort while finding potential alignment on projects that build on the collaboration that exists for energy conservation, ROW utility coordination, LED street lights and fiber network pole attachments.

ERS Recommendation	PSE Role	City Role	Actions to Date
Future System 2:			PSE notes its Smart Grid Initiatives including Automation:
Smart Grid Initiatives (cont'd)			 FLISR (Fault Location, Isolation, Service Restoration) Worked with a consultant to developed requirements/architecture for FLISR tools; evaluating vendors/products in 2014. AMI (Advanced Metering Infrastructure) 16-meter pilot project in CBD implemented in September 2013; results show improvement in receipt of meter reads. Remote Data Acquisition Devices (RDADs) 60 in place; next generation devices expected in 2014; working to integrate RDADs with EMS (Energy Management System).
			Distribution SCADA Switchgear – 4 installed and connected; 8 sites constructed in 2013 but not all had full remote functionality; 12 planned for installation in 2014 together with integration of all switches into EMS; plan presently calls for retrofitting a total of 66 switches to be SCADA equipped in the CBD area.
Future System 3:	PSE maintains a plan for expansion of the system in Bellevue to support growth of the City	The City should engage PSE in an annual planning workshop around future projects	• The annual planning workshop has been held twice; last was 2013; next meeting 2Q 2015. PSE and City staff attend and exchange
Major Project Planning	and the region. However, as lead time to permit	with the intent of understanding the	recommended information; specific tasks are directed.
	larger projects (required to add capacity or	requirements from a City perspective. The	These System Plan planned facilities are included in the updated
	reinforce the City infrastructure) has grown, it	Comprehensive Plan includes an electric	Utilities Element Figure UT-5a.
	requires that the City understand the projects	system plan that can serve as the basis; the	Transmission System Improvements Recently Completed:
	from a more detailed perspective.	 workshop should focus on: Current growth projections and power use in Bellevue Review of current plan applicability (UT-5a) Update of the current plan Develop actions for capacity projects required to initiate siting and permitting activities 	 Ardmore Substation: New distribution substation with looped (redundant) 115kV transmission line (2013) Lake Hills Tap 115kV: Extension to Ardmore Substation with automated transmission switching (2014) In Progress: Lake Hills—Phantom Lake 115kV: New transmission line between existing substations to provide redundant (looped) transmission connection for three substations – permitting in 2014/2015 with planned construction in 2016.

			 Energize Eastside 230kV: New 230kV transmission line(s) and new transmission station in Bellevue to provide local and regional increased system capacity and reliability – permitting in 2015/2016 with planned construction in 2017.
ERS Recommendation	PSE Role	City Role	Actions to Date
Future System 3:	Add transformer banks: • Growth to 125 MVA Initiate: 2012 Need: 2016	Monitor; permit	Will get update at next annual planning workshop 2Q, 2015
Major Projects Update	• Growth to 150 MVA Initiate: 2016 Need: 2020		
Downtown Substations	 Growth to 175 MVA Initiate: 2022 Need: 2026 Growth to 200 MVA Initiate: 2026 Need: Unknown 		
Future System 3:	Add transformer banks: • Growth to 20 MVA Initiate: 2012 Need: 2018	Monitor; permit	Will get update at next annual planning workshop 2Q, 2015
Major Projects Update	• Growth to 40 MVA Initiate: 2022 Need: 2026		On the Near Horizon:
BelRed			 Vernell Substation – New 115kV transmission switching station with local distribution substation for improved transmission system flexibility/reliability and new distribution system capacity to support Spring District development in 2020.
Future System 3:	Add transformer bank: • Growth/reliability Initiate: 2012 Need: 2018	Monitor; permit	Will get update at next annual planning workshop 2Q, 2015
Major Projects Update Somerset/Eastgate			
Future System 3:	Upgrade 115kV line to 230kV. This is EE.	Monitor; permit	Energize Eastside 230kV: New 230kV transmission line(s) and new transmission station in Bellevue to provide local and regional
Major Projects Update 115 kV System	• 50 MVA Need Downtown/Regional Growth Initiate: 2012 Need: 2018-2022		increased system capacity and reliability – permitting in 2015/2016 with planned construction in 2017.
	Add 3 rd transmission feed from the north		The City participated in PSE's Energize Eastside community outreach program mandated by LUC 20.20.255
	Additional 50 MVA Downtown Initiate: 2015 Need: 2020-2024		 The City initiated an Independent Technical Analysis for need PSE applied for an EIS (8/2014) which is underway The City will permit the project through the conditional use permit as an essential public facility

ERS Recommendation	PSE Role	City Role	Actions to Date
Future System 4:	Both Bellevue and PSE work with various developers and companies to identify new	The City should engage with PSE in an annual planning workshop around future	• The annual planning workshop has been held twice; last was 2013; next meeting 2Q, 2015. PSE and City staff attend and exchange
Long Range Planning	potential facilities in Bellevue. There is an opportunity to share and communicate the results of these planning activities.	projects with the intent of synchronizing their growth projections for the City by exchanging information on expected	recommended information; specific tasks are directed. The exchange is meant to be longer-term [than the reliability workshops] planning and well in advance of any specific permitting
	results of these planning detivities.	projects, expected timing of projects, and coordination activities required by PSE and	or development activities.
Dala of the City of Ballanna (C	b A) Futura Custama Assassant Bassant and attack	the City to address these projects.	
	h. 4) Future System Assessment Recommendation nmendations in these sections: Enhanced Role of t		
merades an premimary recon	PSE-WUTC Role		
Role of the City 1:	From a WUTC perspective relative to electric power, cities are considered as any member of	Bellevue's ability to be a knowledgeable stakeholder will require assignment of an	• 2015-2016 budget considered but did not include engineer. At this time city budget for PSE monitoring is deployed for outside legal,
WUTC Interaction	the public. Bellevue's primary interaction with WUTC is one of being an active participant relative to changes in laws and tariffs that may	engineer knowledgeable in the electric power system to foster the City interaction with stakeholders.	tactical and technical experts.
	affect electric system reliability in Washington.		
Role of the City 1a:	, , , , ,	Bellevue's involvement with the WUTC may be one of informing lawmakers and	A new FTE is approved in the 2015-2016 Intergovernmental Relations budget including a portion of position time as the
WUTC Interaction		commissioners of matters that the City believes affect the City's electric reliability	designated individual assigned to electric system matters. The position is expected to be filled 2Q 2015.
		or general electric service. For issues that are of interest to the City:	The City lobbyist monitors electric and energy matters when the Legislature is in session, with support from Intergovernmental Relations and PCD.
		• A designated individual can be assigned to electric system matters. The individual should remain informed of electric system	
		matters related to WUTC	
		White papers can be developed for	
		submittal to WUTC. This provides a means	
		to provide feedback to WUTC without	
		direct response to hearings. Potential policy matters can be advanced this way.	
		policy matters can be advanced this way.	

ERS Recommendation	PSE Role	City Role	Actions to Date
Role of the City 1b:		Bellevue has the opportunity to comment	Only local jurisdiction with staff representation on PSE IRP advisory
		or participate in matters directly affecting	group process—participated in last three IRPs
WUTC Interaction		PSE and their interactions with WUTC:	Actions taken and documented through the annual reliability
		As programs and rate discussions take	workshop; in 2014 workshop for example, Utilities and PSE staff
		place between WUTC and PSE, the City	identified synergistic opportunities to apply smart meter
		has the opportunity to advocate for	technologies in their infrastructure operations (not customer
		positions that support City goals;	meters)
		Comment and participate in various	• The annual reliability workshop has been held 3 times; last was
		programs submitted to WUTC by PSE;	December, 2014; next meeting 2Q, 2015. PSE, City staff and
		where PSE is seeking advisory input from	stakeholders attend; specific tasks are directed and an annual
		stakeholders including the IRP, Smart Grid	reliability report is provided and reviewed.
Dala of the City 2:	Conduct major discussions well in advance of	Plan, and reliability programs.	An automorphism and allowing and allowing the base of the control
Role of the City 2:	permit applications to assure sufficient lead	The City should engage with PSE in an	An outcome of the annual planning workshop has been information An outcome of the annual planning workshop has been information. An outcome of the annual planning workshop has been information.
Maior Duciost Diamains	time to permit larger projects required to add	annual planning workshop around future projects with the intent of a focus on:	exchanged around advance project initiation. Please refer to the
Major Project Planning	capacity or reinforce the City infrastructure	1 ' -	Future System 3: Major Projects Update section.
	capacity of reinforce the city infrastructure	• current growth projections & power use;	
	Engage in annual planning workshop for future	current and updated Plan applicability; Developing actions for connective projects to	
	capacity/expansion projects	 Developing actions for capacity projects to initiate within next 2 years 	
Role of the City 3:	Both Bellevue and PSE work with various	The City should engage with PSE in an	The annual planning workshop has been held twice; last was 2013;
Role of the city 5.	developers and companies to identify new	annual planning workshop around future	next meeting 2Q, 2015. PSE and City staff attend and exchange
Long-Range Planning	potential facilities in Bellevue. There is an	projects with the intent of synchronizing	recommended information; specific tasks are directed. The
Long-Nange Flamming	opportunity to share and communicate the	their growth projections for the City by	exchange is meant to be longer-term [than the reliability
	results of these planning activities.	exchanging information on expected	workshops] planning and well in advance of any specific permitting
	results of these planning activities.	projects, expected timing of projects, and	or development activities.
		coordination activities required by PSE and	or development detivities.
		the City to address these projects.	
Role of the City 4a:	There are opportunities for multiple utilities to	City engage its utility partners to identify	The City's Right-of-Way division hosts monthly utility coordination
	take advantage of projects being performed by	new projects to attempt to maximize	meetings to which all parties with Bellevue Franchise Agreements
Multi-Utility Planning	one of the utilities. This action also represents a	projects in the ROW.	and Bellevue ROW Agreements are invited. PSE participates as a
	potential means to advance undergrounding of		matter of course in these meetings.
	circuits if PSE can take advantage of trenching		
	to allow conduits for future use.		

ERS Recommendation	PSE Role	City Role	Actions to Date
Role of the City 4b:	There are opportunities for multiple utilities to	The City can take advantage of projects that	Transportation capital projects work with all power, gas and
	take advantage of projects being performed by	require trenching to place conduit for	telecommunications utilities during the design process to provide
Multi-Utility Planning	one of the utilities. This action also represents a	future use of potential undergrounding. The	opportunities for coordinated construction of new or relocated
	potential means to advance undergrounding of	existence of conduit may allow for more	infrastructure. It is most cost-effective when undergrounding
	circuits if PSE can take advantage of trenching	economic alternatives to undergrounding in	utilities to have them utilize a common trench line for the backbone
	to allow conduits for future use.	the future. Where trenching occurs, city	of their systems. Recent and current projects where the city has
		coordinates the placement of conduit,	initiated the planning and installation of underground systems include:
			PW-R-160 NE 4 th Street Extension – 116 th to 120 th Avenues NE
			PW-R-160 NE 4 Street Extension = 110 to 120 Avenues NE PW-R-164 120 th Avenue NE Stage 2 — NE 8 th Street to NE 12 th
			PW-R-168 120 th Avenue NE Stage 3 NE 12 th to NE 16 th Streets
			PW-R-166 124 th Avenue NE – NE Spring Blvd to NE 18 th Street and
Role of the City 5:	Develop a more formal process related to	Develop a more formal process related to	 The recently completed 120th Avenue NE Stage 1 project. City emergency operations staff report that they and PSE staff have
Role of the city 5.	emergency response & support activities which	emergency response & support activities;	developed a model of pre-event coordination for forecasted storms
Emergency Response	may include locating damage, coordination of	agreement or procedure for communication	that may affect the power systems in Bellevue. Staff coordinate on-
Capability	access to areas of damage, access to PSE outage	and coordination during large scale events	call contacts, contact numbers and work hours in advance so that
capability	information, coordination of recovery plans,		Bellevue-specific contacts can be made and information exchanged
	emergency support to people in need.		in the shortest time possible. Staff are continuing to explore the
			possibility of obtaining site-specific (address) outage information,
	During storm events, dedicated PSE staff are		possibly with shared technology.
	assigned to the local Redmond storm base. PSE		During non-storm event outages, PSE keeps city staff in
	staff are directly linked to dedicated city		Transportation, Utilities and PCD informed as to their status. When
	personnel staffing the EOC.		PSE has ongoing actions taking place they notify relevant city staff.
			City emergency management staff are formalizing communications
			emergency protocols between organizations MOU addresses the goal
			of optimizing City/PSE relationship on coordination and
			communication:
			The Office of Emergency Management participated in several diagnosis as least fall with DCF as a public at hair Outroe Management
			discussions last fall with PSE regarding their Outage Management
			System.

ERS Recommendation	PSE Role	City Role	Actions to Date
			 http://pse.com/accountsandservices/ServiceAlert/Pages/Outage-Map.aspx - The previous link is to the improved tool that PSE is leveraging to share power outage information with public. The Office of Emergency Management used this tool twice during the 2014-2015 Winter Storm Season to support incident operations in the City. While the tool has been greatly enhanced and has allowed for further community communications and emergency response more improvements have been suggested to PSE Emergency Management representatives. One capability suggested included the ability to further sort and filter through large amounts of data potentially related to power outage in and near the City.
			City Public Information Officers visited PSE in December 2014 to better understand the role and the communication structure between PSE and City Emergency Operations Center and Incident Command Structure during emergency incidents.
			The Office of Emergency Management has been meeting monthly with PSE Emergency Management representatives through the King County Zone 1 Emergency Management Group and the Emergency Management Advisory Committee (EMAC)/ Region 6 Homeland Security Council. These are important opportunities to leverage the knowledge of many disciplines and organizations across King County in relation to how PSE prepares for incidents that may affect their systems that will impact the City of Bellevue.
Measurement and Monitorin	g (Ch. 5)) SUMMARY nmendations in these sections: Metrics (5.1) and S	takeholder Communication (5.2)	
Measure/ Monitoring 1:	PSE has ongoing reliability initiatives and	Table 7 Proposed Metrics:	The annual reliability workshop has been held 3 times; last was
Metrics: • Performance-based • Outage-based	performs system-wide and targeted projects to improve system reliability.	 Bellevue Circuits of Concern Downtown Reliability Reliability Project Effectiveness 	December, 2014; next meeting 2Q, 2015. These metrics are reported by PSE in its annual reliability report (required by the existing MOU) and include SAIFI/SAIDI performance;
Design-based Growth-based		System RedundancyAutomation UtilizationPower Demand	Bellevue SAIDI/SAIFI data shows better performance than for rest of PSE service area.

ERS Recommendation	PSE Role	City Role	Actions to Date
Measurement and		The City has many avenues available for	City personnel meet and coordinate with PSE personnel to
Monitoring 2:		communicating with its various constituents	understand and support PSE's implementation capabilities of their
		regarding the electric reliability initiative. A	computerized outage management system. This was combined in
Stakeholder		major concern of the various stakeholders is	the MOU with Item 6 into one provision addressing Coordination
Communication		the timeliness of information on matters	and Communication.
		that affect residents and businesses in	Improved proactive communication has occurred between the
		Bellevue. Information can be provided for	city's operational departments, its Emergency Operations Center,
		the following:	and PSE around coordination emergency response protocols and
			supporting PSE's community communications efforts.
		Overall electrical performance through	
		the PSE reliability report and various	
		statistical analyses that can be performed	
		by the City	
		Early notification of major growth and	
		projects affecting the City electric system	
		based on planning meetings with PSE	
		Information on OMS and emergency	
		response in normal and storm conditions	
		Information relative to identifying critical	
		facilities so that PSE is aware of these	
		prior to emergency events	
		The C'll has the country to the decidence	
		The City has the opportunity to develop a	
		communications plan around electric	
		system performance through the use and	
		publishing of the metrics. The City may choose to combine these with other forms	
		of communication to provide a standard	
		form of update and status. The City website provides a vehicle to communicate to its	
		constituents as an informed stakeholder.	
		constituents as an imormed stakeholder.	