



CORNER SEGMENTS

NOTES:

1. PRECAST TRAFFIC CURB SHALL BE INSTALLED WITH AN EAS-60 TWO PART EPOXY. SEE COB SPECIFICATION SECTION 8-09.
2. EPOXY SHALL BE PLACED UNDER THE BEARING SURFACE OF THE PRECAST TRAFFIC CURB.
3. APPLY SUFFICIENT EPOXY TO ENSURE SQUEEZE-OUT OF 50% PER EACH SIDE OF EACH CURB SECTION.



PRECAST CONCRETE SLOPED MOUNTABLE CURB

DRAWING NUMBER	TE-9D
SCALE	NONE
REVISION DATE	03/15
DEPARTMENT	TRANS