



**City of Bellevue  
Development Services Department  
Land Use Staff Report**

---

**Proposal Name:** Schaff Slope Buffer Modification

**Proposal Address:** 4326 Lake Washington Blvd. SE


**Proposal Description:** Land Use review of a proposal to modify a top-of-slope buffer for the expansion of a single-family residence.


**File Number:** 10-109872-LO

**Applicant:** Craig Schaff, Property Owner

**Decisions Included** Critical Areas Land Use Permit  
(Process II. 20.30P)

**Planner:** Reilly Pittman, Land Use Planner

**State Environmental Policy Act  
Threshold Determination:** Exempt  
  
Carol V. Helland, Environmental Coordinator  
Development Services Department

**Director's Decision:** **Approval with Conditions**  
Michael A. Brennan, Director  
Development Services Department  
By:   
Carol V. Helland, Land Use Director

---

**Application Date:** April 16, 2010  
**Notice of Application Date:** April 29, 2010  
**Decision Publication Date:** July 8, 2010  
**Project/SEPA Appeal Deadline:** July 22, 2010

---

For information on how to appeal a proposal, visit Development Services Center at City Hall or call (425) 452-6800. Comments on State Environmental Policy Act (SEPA) Determinations can be made with or without appealing the proposal within the noted comment period for a SEPA Determination. Appeal of the Decision must be received in the City's Clerk's Office by 5 PM on the date noted for appeal of the decision.


## CONTENTS

I.	Proposal Description.....	Pg 3
II.	Site Description, Zoning & Land Use Context.....	Pg 3-5
III.	Consistency with Land Use Code Requirements.....	Pg 5-7
IV.	Public Notice & Comment.....	Pg 7
V.	Summary of Technical Review.....	Pg 7
VI.	Changes to Proposal Due to Staff Review.....	Pg 7
VII.	Decision Criteria.....	Pg 7-11
VIII.	Conclusion and Decision.....	Pg 11-12
IX.	Conditions of Approval.....	Pg 12-14
X.	Attachments.....	Pg 14

## I. Proposal Description

A covered entry over a deck and expansion of the house for increased habitable space is proposed within the top-of-slope buffer to an existing house. Total house expansion is 498 square feet, of which approximately 81 square feet of house and 211 square feet of covered porch entry are within the top-of-slope buffer. The majority of the remodel is occurring within the footprint of the existing house and is not modifying any critical area, buffer, or structure setback with the exception of the proposed expansions. A Critical Area Land Use Permit is required to approve a modification or reduction of a top-of-slope buffer to allow the proposed expansion. See Figure 1 below for a site plan showing the proposed activities.

Figure 1




## II. Site Description, Zoning, Land Use and Critical Areas

### A. Site Description

The project site is located at 4326 Lake Washington Blvd. SE in the Newport area of the City. The site is located in the NW quadrant of Section 16, Township 24 North, Range 5 East. The property is a narrow, triangular shaped lot adjacent to Lake Washington Blvd. to the west, the vacated Burlington Northern Santa Fe Railway line to the east, and another single-family zoned property to the north. The surrounding neighborhood is single-family residentially zoned property. The regulated steep slopes on the site are found along the western property line between Lake Washington Blvd. and the existing house. These slopes are 40 percent or greater in slope which then flattens out where the existing development is located. Slopes to the east of the site do not meet requirements to be classified as a critical area. See Figure 2 for existing site condition.

Figure 2



**B. Zoning**

The property is zoned R-2.5, single-family residential and is located in the Critical Areas Overlay District. The surrounding properties are also zoned R-2.5 and R-5. The proposed work is allowed in the R-2.5 zone.

**C. Land Use Context**

The property has a Comprehensive plan Land Use Designation of SF-M (Single Family Medium Density).

**D. Critical Areas On-Site and Regulations**

**i. Geologic Hazard Areas**

Geologic hazards pose a threat to the health and safety of citizens when commercial, residential, or industrial development is inappropriately sited in areas of significant hazard. Some geologic hazards can be reduced or mitigated by engineering, design, or modified construction practices. When technology cannot reduce risks to acceptable levels, building in geologically hazardous areas is best avoided (WAC 365-190).

Steep slopes may serve several other functions and possess other values for the City and its residents. Several of Bellevue’s remaining large blocks of forest are located in steep slope areas, providing habitat for a variety of wildlife species and important linkages between habitat areas in the City. These steep slope areas also act as conduits for groundwater, which drains from hillsides to provide a water source for the City’s wetlands and stream systems. Vegetated steep slopes also provide a visual amenity in the City, providing a “green” backdrop for urbanized areas enhancing property values and buffering urban development.

**ii. Critical Areas Overlay District/Critical Area Land Use Permit**

A Critical Area Land Use Permit (CALUP) is required as the applicant is requesting to reduce a top-of-slope buffer. These modifications can only be approved through a critical area report submitted under a CALUP.

**III. Consistency with Land Use Code Requirements:**

**A. Zoning District Dimensional Requirements:**

The proposal generally meets the R-2.5 zoning dimensional requirements found in LUC 20.20.010. The proposed new residence will be evaluated for conformance with zoning requirements, as part of the required building permit review. The proposed improvements must be found in conformance with zoning requirements regardless of the approval granted under this Critical Areas Land Use Permit. See Conditions of Approval in Section IX of this report.

**B. Critical Areas Requirements LUC 20.25H:**


The City of Bellevue Land Use Code Critical Areas Overlay District (LUC 20.25H) establishes performance standards and procedures that apply to development on any site which contains in whole or in part any portion designated as critical area, critical area buffer or structure setback from a critical area or buffer. The project is subject to the performance standards found in LUC 20.25H, as specified in the table below

<b>Critical Area</b>	<b>Geologic Hazard- Steep Slopes</b>
<b>Performance Standards</b>	20.25H.125 20.25H.230

**i. Consistency With LUC 20.25H.230**

A 50-foot buffer is required from the top-of-slope of any steep slope critical area on a developed site. The existing house is located approximately 23 feet away or less from the top-of-slope. See Figure 3 below for steep slope critical areas on the site.

**Figure 3**



The proposed expansion maintains the line of the existing foundation and does not expand the house any closer to the top-of-slope; however, the expansion is outside the existing footprint, within the buffer. The proposed activity requires a critical areas report as part of the application for a Critical Area Land Use Permit. As this is a proposal to modify the required top-of-slope buffer for the proposed development, the applicant has obtained the services of a qualified geotechnical engineering consultant to study the site and document the observed conditions. Staff has reviewed the following documents:

- Geotechnical Engineering Study dated April 5, 2010 prepared by Geotech Consultants, Inc. and revision dated May 26, 2010

This geotechnical analysis indicates that there are “no indications of instability” in the slopes located on the site (Pg. 2). As stated above, the expansion of the house is maintaining the existing line of the foundation and is no closer than “15 feet” to the steep slope (Pg. 8). The area between the existing house and west facing steep slope will “remain undisturbed” (Pg. 3); the area where the proposed expansion is located is currently covered by asphalt paving. As a result of the analysis in the geotech report, the engineer has found that the planned development will “not adversely affect the stability of the steep slope,” provided their recommendations are followed (Pg. 9).

#### Consistency With LUC 20.25H.125

The performance standards found in LUC 20.25H.125 are being met as the majority of the new residence is being constructed within disturbed areas already existing on the

site and does not alter existing topography or remove vegetation on the site. The geotechnical engineer for the project has reviewed the plans and found that the proposed development will not impact slope stability. No structure is proposed to be constructed within a steep slope; no rockeries or retaining walls are proposed. Part of the proposed improvements is to direct drainage from the house into a drainage system which will prevent runoff reaching the steep slope which could lead to erosion. The proposed project complies with the performance standards found in LUC 20.25H.125.

#### **IV. Public Notice and Comment**

Application Date:	April 16, 2010
Public Notice (500 feet):	April 29, 2010
Minimum Comment Period:	May 13, 2010

The Notice of Application for this project was published in the City of Bellevue weekly permit bulletin April 29, 2010. It was mailed to property owners within 500 feet of the project site. No comments were received.

#### **V. Summary of Technical Reviews**

##### **A. Clearing and Grading**

The Clearing and Grading Division of the Development Services Department has reviewed the proposed site development for compliance with Clearing and Grading codes and standards. The Clearing and Grading staff found no issues with the proposed development and has approved the application.

#### **VI. Changes to Proposal Due to Staff Review**

Staff requested the geotech to recommend a minimum buffer width from the top-of-slope to allow for the proposed construction and future access and maintenance around the house. The applicant provided the requested recommendation in a revised geotech report.

#### **VII. Decision Criteria**

##### **A. 20.25H.145 Critical areas report – Approval of modification.**

**Modifications to geologic hazard critical areas and critical area buffers shall only be approved if the Director determines that the modification:**

- 1. Will not increase the threat of the geological hazard to adjacent properties over conditions that would exist if the provisions of this part were not modified;**

The project geotechnical engineer reviewed the proposed modifications and found that the proposals will “not adversely affect the stability of the steep slope,” provided their recommendations are followed (Pg. 9). The proposed expansion of the residence will not be any closer to the top-of-slope than the existing residence.

- 2. Will not adversely impact other critical areas;**

A top-of-slope buffer from the steep slope above Lake Washington Blvd. SE is being modified to allow for the expansion of an existing house and to maintain access around the house for maintenance purposes. There are no other critical areas in the vicinity other than steep slopes.

- 3. Is designed so that the hazard to the project is eliminated or mitigated to a level equal to or less than would exist if the provisions of this part were not modified;**

The project geotechnical engineer has reviewed the proposed modifications and found that the proposals are suitable given the geological characteristics of the property. In addition, the geotech has stated that the proposed development may “improve slope stability” as site runoff will be directed away from the steep slope (Pg. 9). On page 8 and 9 of the report the geotech has recommended the following in order to limit the risk of a landslide on the steep slope:

- Leave the steep slope, including its existing vegetated cover, undisturbed.
- Place no new fill in the area between the house and the steep slope. If desired, some of the existing fill could be removed in this area, provided the excavation stops at the face of the steep slope. Soil resulting from excavation should either be used for backfill on the east side of the house, or be hauled off the site.
- Excavate all new footings, including those for the deck down to dense, native soil.
- Avoid discharging concentrated water from impervious areas toward the slope.

These recommendations will be conditions of approval. See Conditions of Approval in Section IX of this report.

- 4. Is certified as safe as designed and under anticipated conditions by a qualified engineer or geologist, licensed in the state of Washington;**

The project geotechnical engineer has reviewed the proposed modifications. In addition to the above recommendations the geotech also recommended that a “minimum 10-foot buffer is acceptable” from the top-of-slope (Pg. 9) for the proposed development. Provided their recommendations are followed the project engineer has stated that the proposal will not adversely affect the slope stability.

- 5. The applicant provides a geotechnical report prepared by a qualified professional demonstrating that modification of the critical area or critical area buffer will have no adverse impacts on stability of any adjacent slopes, and**

**will not impact stability of any existing structures. Geotechnical reporting standards shall comply with requirements developed by the Director in City of Bellevue Submittal Requirements Sheet 25, Geotechnical Report and Stability Analysis Requirements, now or as hereafter amended;**

The submitted geotechnical report meets City of Bellevue requirements.

- 6. Any modification complies with recommendations of the geotechnical support with respect to best management practices, construction techniques or other recommendations; and**

As described above, the geotech engineer has provided recommendations on page 8 and 9 which will be followed. In addition the geotech has recommended a 10-foot buffer from the top-of-slope of the steep slope critical area.

- 7. The proposed modification to the critical area or critical area buffer with any associated mitigation does not significantly impact habitat associated with species of local importance, or such habitat that could reasonably be expected to exist during the anticipated life of the development proposal if the area were regulated under this part.**

The proposed development is being placed over existing impervious surfaces and improved areas. No vegetation is being removed by the proposal. Mitigation planting for the buffer modification is being provided along the top of the slope.

#### **B. 20.25H.255.B Decision Criteria – Proposals to Reduce Regulated Critical Area Buffers**

**The Director may approve, or approve with modifications, a proposal to reduce the regulated critical area buffer on a site where the applicant demonstrates:**

- 1. The proposal includes plans for restoration of degraded critical area or critical area buffer functions which demonstrate a net gain in overall critical area or critical area buffer functions;**

A 500 square foot area along the top-of-slope of the steep slope critical area is proposed to be planted with vegetation drawn from the City planting templates for steep slopes. The proposed planting area achieves over a 1:1 ratio to the square footage of slope buffer proposed to be modified. See Conditions of Approval in Section IX of this report.

- 2. The proposal includes plans for restoration of degraded critical area or critical area buffer functions which demonstrate a net gain in the most important critical area or critical area buffer functions to the ecosystem in which they exist;**

Slope stability and risk of a landslide will be improved by directing storm water away

from the slope by addition of new vegetation at the top-of-slope and by not increasing the area of disturbance beyond what currently exists.

- 3. The proposal includes a net gain in stormwater quality function by the critical area buffer or by elements of the development proposal outside of the reduced regulated critical area buffer;**

Water from roof runoff and other runoff will be directed into storm systems to prevent water from reaching the steep slope critical area.

- 4. Adequate resources to ensure completion of any required restoration, mitigation and monitoring efforts;**

The restoration planting will be monitored for a period of three years with reports submitted once a year. A performance surety for maintenance and monitoring will be required based on the cost estimate of plants, material, and labor. The performance surety will be released after three years assuming restoration has been successful. See Conditions of Approval in Section IX of this report.

- 5. The modifications and performance standards included in the proposal are not detrimental to the functions and values of critical area and critical area buffers off-site; and**

The modifications and performance measures in this proposal are not detrimental to the functions and values of the steep slopes on-site.

- 6. The resulting development is compatible with other uses and development in the same land use district.**

Expansion of a single-family house is allowed in this zone and is compatible with adjacent land uses.

#### **C. 20.30P.140 Critical Area Land Use Permit Decision Criteria – Decision Criteria**

**The Director may approve, or approve with modifications an application for a Critical Area Land Use Permit if:**

- 1. The proposal obtains all other permits required by the Land Use Code;**

The applicant must obtain a building permit. See Conditions of Approval in Section IX of this report.

- 2. The proposal utilizes to the maximum extent possible the best available construction, design and development techniques which result in the least impact on the critical area and critical area buffer;**

The proposal is consistent with required performance standards for projects in steep

slope critical areas. The proposed development is maintaining the existing foundation line and is not encroaching further into the slope buffer than currently exists.

3. **The proposal incorporates the performance standards of Part 20.25H to the maximum extent applicable, and ;**

As discussed in Section III of this report, the applicable performance standards of LUC Section 20.25H are being met.

4. **The proposal will be served by adequate public facilities including street, fire protection, and utilities; and;**

The site is already services by adequate public facilities.

5. **The proposal includes a mitigation or restoration plan consistent with the requirements of LUC Section 20.25H.210; and**

The proposed mitigation planting is per the planting templates found in the City's Critical Areas Handbook. Maintenance and monitoring is required for 3 years and will be guaranteed by a performance surety. A yearly monitoring report with photograph documentation shall be submitted in order to release the performance surety after 3 years . See Conditions of Approval in Section IX of this report.

6. **The proposal complies with other applicable requirements of this code.**

As discussed in this report, the proposal complies with all other applicable requirements of the Land Use Code.

## VIII. **Conclusion and Decision**

After conducting the various administrative reviews associated with this proposal, including Land Use Code consistency, City Code and Standard compliance reviews, the Director of the Development Services Department does hereby **approve with conditions** the reduction of the 50-foot top-of-slope buffer for the expansion of an existing home and construction of a covered entry porch. This approval does not reduce the entire top-of-slope buffer to 10 feet; future development may require geotechnical evaluation and further Critical Areas Land Use Permit approvals. **Approval of this Critical Areas Land Use Permit does not constitute a permit for construction. A building permit and other development permits are required and all plans are subject to review for compliance with applicable City of Bellevue codes and standards.**

**Note- Expiration of Approval:** In accordance with LUC 20.30P.150 a Critical Areas Land Use Permit automatically expires and is void if the applicant fails to file for a building permit or other necessary development permits within one year of the effective date of the approval.

**IX. Conditions of Approval**

**The applicant shall comply with all applicable Bellevue City Codes and Ordinances including but not limited to:**

<u>Applicable Ordinances</u>	<u>Contact Person</u>
Clearing and Grading Code- BCC 23.76	Savina Uzunow, 425-452-7860
Land Use Code- BCC Title 20	Reilly Pittman, 425-452-4350
Noise Control- BCC 9.18	Reilly Pittman, 425-452-2973

**The following conditions are imposed under the Bellevue City Code or SEPA authority referenced:**

- 1. Building Permit Required:** Approval of this Critical Areas Land Use Permit does not constitute an approval of a development permit. Application for a building permit and any other necessary permits must be submitted and approved. Plans submitted as part of any permit application shall be consistent with the activity permitted under this approval. As part of building permit review the proposal must be found in conformance with all zoning dimensional standards and code requirements.

Authority: Land Use Code 20.30P.140  
Reviewer: Reilly Pittman, Development Services Department

- 2. Extent of Buffer Modification:** The modification of the top-of-slope buffer approved under this permit allows an approximately 211 square foot covered entry porch and 81 square foot home addition to be built within the top-of-slope buffer. A further buffer modification of approximately 500 square feet (10ft x 50ft) is allowed for maintenance and access around the house, provided in no place the buffer is reduced below 10-feet from the top-of-slope.

Authority: Land Use Code 20.30P.140  
Reviewer: Reilly Pittman, Development Services Department

- 3. Mitigation Planting:** Per the submitted plans, a 500 square foot area of planting is required as mitigation for the buffer modification approved by this decision.

Authority: Land Use Code 20.30P.140  
Reviewer: Reilly Pittman, Development Services Department

- 4. Cost Estimate and Performance Surety:** At time of building permit application, a cost estimate based on the cost of labor and materials as part of the restoration plan will be required. This cost estimate will be the basis for determining the value needed for a required 3-year performance surety for maintenance and monitoring of the planting.

Authority: Land Use Code 20.30P.140

Reviewer: Reilly Pittman, Development Services Department

5. **Land Use Inspection:** Following installation of planting the applicant shall contact Land Use staff to inspect the planting area. At the end of 3 years, inspection by Land Use staff is required to release the performance surety. Staff will need to find that the plants are in a healthy and growing condition.

Authority: Land Use Code 20.30P.140

Reviewer: Reilly Pittman, Development Services Department

6. **Maintenance and Monitoring:** A report on plant health, survival, and maintenance activity with photo documentation shall be submitted yearly for three years. Photos shall be taken from 3 different points to be established on the plans. Reports shall be submitted to the Land Use Department in order to release the performance surety.

Authority: Land Use Code 20.30P.140

Reviewer: Reilly Pittman, Development Services Department

7. **Geotechnical Recommendations:** Construction of the proposed improvements shall meet the following recommendations from the geotechnical report:

- Leave the steep slope, including its existing vegetated cover, undisturbed.
- Place no new fill in the area between the house and the steep slope. If desired, some of the existing fill could be removed in this area, provided the excavation stops at the face of the steep slope. Soil resulting from excavation should either be used for backfill on the east side of the house, or be hauled off the site.
- Excavate all new footings, including those for the deck down to dense, native soil.
- Avoid discharging concentrated water from impervious areas toward the slope.

Authority: Land Use Code 20.25H.145

Reviewer: Reilly Pittman, Development Services Department

8. **Hold Harmless Agreement:** The applicant shall submit a hold harmless agreement in a form approved by the City Attorney which releases the City from liability for any damage arising from the location of improvements within a critical area buffer in accordance with LUC 20.30P.170. The hold harmless agreement is required to be recorded with King County prior to building permit issuance.

Authority: Land Use Code 20.30P.170

Reviewer: Reilly Pittman, Development Services Department

9. **Noise Control:** Noise related to construction is exempt from the provisions of BCC 9.18 between the hours of 7 am to 6 pm Monday through Friday and 9 am to 6 pm on Saturdays, except for Federal holidays and as further defined by the Bellevue City Code.

Noise emanating from construction is prohibited on Sundays or legal holidays unless expanded hours of operation are specifically authorized in advance. Requests for construction hour extension must be done in advance with submittal of a construction noise expanded exempt hours permit.

Authority: Bellevue City Code 9.18


Reviewer: Reilly Pittman, Development Services Department

**X. Attachments:**

1. Project Plans submitted April 16, 2010 – Enclosed
2. Critical Area Report Narrative submitted April 16, 2010 – Enclosed
3. Geotechnical Report revised May 26, 2010 – Enclosed
4. Application and other project information submitted – In File

# Schaff Slope Buffer Modification Vicinity Map

## File Number: 10-109872-LO





## Critical Areas Report

Received  
APR 10 2010  
Permit Processing

**History:** The original home was constructed on 1912 along the shores of Lake Washington. The home was moved to the current site, just East of Lake Washington Blvd. SW, when the Newport Shores housing area was developed. The property has steep slopes both to the West and East. The area to the West of the home slopes down to Lake Washington Blvd. SW. The area toward the East is a berm that was created when the railroad tracks were laid decades ago. No slope instability is evident on any of the site. This proposal would provide for an infill of the existing foundation footprint as shown in the accompanying site plan. This proposed infill is parallel to the edge of the critical area on both sides. (Making a "T- shaped" foundation square in plan) In addition we are proposing a covered entry deck on the North side of the existing home. The entry deck construction utilizes pier pad and column support to minimize ground disturbance to an absolute minimum.

All proposed expansion to the existing foundation is on flat terrain over areas that are currently impervious. This proposal will not negatively impact the surrounding steep slopes in any way.

This proposed footprint additions would require reduction of the steep slope buffers as defined by the Critical Areas regulations. All combined, these areas will be 498 square feet.

**Performance Standards:** note to reviewer: standards in italic, proposal in bold typeface.

*A. Structures and improvements shall minimize alterations to the natural contour of the slope, and foundations shall be tiered where possible to conform to existing topography;*

**The proposed design does not alter the existing topography in any way.**

*B. Structures and improvements shall be located to preserve the most critical portion of the site and it's natural landforms and vegetation;*

**The proposed design does not remove any vegetation, all areas for new construction are currently impervious and flat.**

*C. The proposed development shall not result in greater risk or a need for increased buffers on neighboring properties;*

**Per the enclosed soils report, the proposed project does not increase risk of increasing instability to the surrounding critical areas. No neighboring properties**

**are affected by this proposal because of existing topography. The top of the property is bordered by an abandoned railway and bottom Lake Washington Blvd.**

*D. the use of retaining walls that allow the maintenance of existing natural slope area is preferred over graded artificial slopes where graded slopes would result in increased disturbance as compared to use of retaining wall;*

**No new retaining walls are proposed with this project. The existing retaining wall on site will remain untouched by this development. (this represents the minimum possible disturbance to the site)**

*E. Development shall be designed to minimize impervious surfaces within the critical area and critical area buffer;*

**The proposed development will not increase impervious area period. All development is concentrated on top of existing gravel parking area or exterior stone stairway. The proposed entry deck utilizes pier pad and column construction to minimize site disturbance.**

*F. Where change in grade outside the building footprint is necessary, the retention system should be stepped and regrading should be designed to minimize topographic modification. On slopes in excess of 40 percent, grading for yard area may be disallowed where inconsistent with this criteria;*

**As per A. above, no grade changes are proposed period.**

*G. Building foundation walls shall be utilized as retaining walls rather than rockeries or retaining structures built separately and away from the building wherever feasible. Freestanding retaining devices are only permitted when they cannot be designed as structural elements of the building foundation;*

**As per D. above, no new retaining walls are proposed with this development. Existing retaining structures will remain as they represent the minimum possible disturbance to the site (and least risk).**

*H. On slopes in excess of 40 percent, use of pole-type construction which conforms to the existing topography is required where feasible. If pole-type construction is not technically feasible, the structure must be tiered to conform to the existing topography and to minimize topographic modification;*

**No construction is proposed in any areas of 40% grade so this performance standard is not applicable. (All areas of proposed construction are nearly flat)**

*I. On slopes in excess of 40 percent, piled deck support structures are required where technically feasible for parking or garages over fill-based construction types;*

**Not applicable to this application. (Existing garage is outside the critical area buffers)**

*J. Areas of new permanent disturbance and all areas of temporary disturbance shall be mitigated and or restored pursuant to a mitigation and restoration plan meeting the requirements of LUC 20.25H.210.*

**See attached Mitigation Plan.**

*LUC Section 20.25H.210 Mitigation and Restoration:*

**See attached Mitigation plan.**

*20.25H.250.B Minimum Critical Areas Report Requirements:*

**As per the enclosed Geotechnical report, this proposal does not negatively impact the critical area buffers in any way. Buffer effectiveness will be improved by utilization of gutter and downspout drainage collection. This water will tight lined to the existing approved discharge site near the site entrance location. (See enclosed Mitigation plan for specific location) All site disturbance is proposed in areas that are currently flat and impervious. The buffer area does not primarily drain down the steep slope area (it drains to the North and not to the West down the steep slope) So the buffer area does not actually significantly contribute to the stability of the steep slope.**

*20.30P.140 Critical Areas Land Use Permit Decision Criteria:*

*i. The proposal obtains all other permits required by the Land Use Code;*  
**Building permit application has already been applied for. Permit will not be issued without this approval.**

*ii. The proposal utilizes the best available construction, design and development techniques which result in the least impact to the critical area and buffer;*  
**As per the narrative above, this proposal does not negatively impact the critical area, while the mitigation improves stability of the steep slopes.**

*iii. The proposal incorporates the performance standards of LUC 20.25*  
**Please see performance standards response on page 1-2 or this document.**

*iv. The proposal is served by adequate public facilities, including streets, fire protection and utilities;*  
**The property is currently served by all the above public facilities.**

*v. The proposal includes a mitigation or restoration plan consistent with LUC 20.25H.210;*  
**Please see the attached mitigation plan (again).**

*vi. The proposal complies with other applicable requirements of the Land Use Code.*  
**This item is repetitive, see i. above.**

May 26, 2010

JN 09310

Craig Schaff  
4326 Lake Washington Boulevard Southeast  
Bellevue, Washington 98006

Subject: **Geotechnical Engineering Report**  
Proposed Additions and New Deck  
Schaff Residence  
4326 Lake Washington Boulevard Southeast  
Bellevue, Washington  
Bellevue File No. 09-124957-DC

Dear Mr. Schaff:

*via email*

This geotechnical engineering report is intended to be submitted to the City of Bellevue with the Critical Areas Report being prepared for your project.

## 1.0 INTRODUCTION

**1.1 Overview:** Proposed Additions and New Deck  
Schaff Residence  
4326 Lake Washington Boulevard Southeast  
Bellevue, Washington  
Bellevue File No. 09-124957-DC

Geotech Consultants, Inc. previously prepared a geotechnical assessment for the project dated January 6, 2010.

**1.2 Background:** A detached garage is near completion on the northeastern portion of the property under a separate permit. The proposed project related to the existing residence involves a remodel that would include construction of two small additions and a covered deck on the north side of the current structure. The two small additions will be constructed to "fill in" the northeast and northwest corners of the house. The northeastern addition will be two stories constructed over a crawl space, which will avoid the need to excavate fully to the level of the existing basement floor. The northwestern addition will consist of two floors over the basement floor and will cover the area currently occupied by the concrete steps that rise to the front entrance. The covered deck is to extend approximately 8 feet northward from the existing house's footprint. Most of the area to be covered by the deck is already paved parking. At its closest point, the new deck will be 15 feet from the steep slope located on the western side of the site. The only exception to this will be the eastern approximately one-third of the deck, which will be constructed in an area currently covered by bare soil. This portion of the deck will be adjacent to the planned northeastern addition, and is over 30 feet from the western slope.

**1.3 Purpose and Scope of Services:** We previously prepared an abbreviated geotechnical assessment for this project dated January 6, 2010. In order to prepare this current report, we have visited the site on two separate occasions to observe the existing conditions and assess the exposed geology, corresponded with the project team multiple times regarding the planned construction, reviewed the February 19, 2010 *Revision Request #1* prepared by the City of Bellevue, and conducted a slope stability analysis.

Permitting

**1.4 Investigations Summary:** During our visits to the site we have been able to explore the subsurface conditions by close observation of soil exposures along the eastern property line, in the temporary excavations made for the detached garage, and in the cut slope located to the west of the planned building area. We were able to assess the depth to dense soil conditions near the northwestern, downslope corner of the house by probing. Additional geologic information for the site vicinity was available from a geotechnical study that our firm previously conducted at 4306 – 120<sup>th</sup> Avenue Southeast, to the east of the site. For that study, we conducted four test pits. The conditions encountered in the on-site and nearby explorations are discussed below in sub-sections 2.3 and 2.4.

**1.5 Report Overview:** This report presents geotechnical considerations for foundations, drainage and slope stability related to the proposed new construction.

Attached to the end of the report are a Vicinity Map, Site Plan, Footing Drain Detail and Results of Slope Stability Analyses.

## 2.0 SITE CONDITIONS

**2.1 Location and Surface Conditions:** The subject property is located on the east side of Lake Washington Boulevard Northeast, just east of the Newport Shores subdivision. The location of the site is shown on the Vicinity Map attached to the end of this report.

The site is a narrow, triangular-shaped lot, with Lake Washington Boulevard Southeast forming the angled western property line. The property contains the existing residence located in the center of the lot, and a new detached garage situated in the northeast corner of the site. The majority of the property slopes gently to moderately down toward the west. A paved driveway extends up to the garage and house from Lake Washington Boulevard Southeast starting near the northwestern property corner. Along the east edge of the lot is a short slope that rises to the adjacent property, which is old railroad right-of-way. This slope is generally less than 10 feet in height and has been oversteepened by past excavation in conjunction with landscaping and a previous parking space that was located to the east of the house. The area north of the house is covered with asphalt and concrete pavement. Along the west side of the house is a small covered area and landscaping. West of this is a steep slope that declines to the open ditch that runs along the eastern edge of Lake Washington Boulevard Southeast. This slope has a height of 15 to 20 feet and is steeply inclined. The majority of the slope is located within the street right-of-way. The upper two-thirds of the slope has an inclination of approximately 1:1 (Horizontal:Vertical) and is covered with mature underbrush. The lower one-third of the slope is slightly steeper, and appears to have been more recently disturbed, likely in conjunction with maintenance of the ditch and possible utility installation, as there is a fire hydrant at the toe of the slope. This western slope is much steeper than surrounding natural slopes; it is obvious that the slope was created by excavation for Lake Washington Boulevard Southeast and the ditch located alongside it.

There are no indications of instability in the slopes located on both sides of the site.

**2.2 Geologic Setting:** The west-facing ground on which the site is located is underlain by glacial till, which is a glacially-compressed mixture of gravel, silt and fine-grained sand. The site is mapped to be underlain by this geologic unit on the *Geologic Map of Surficial Deposits in the Seattle Quadrangle* (Yount, et. al, 1993). In undisturbed conditions, glacial till is overlain by one to 2 feet of weathered till and organic topsoil. Glacial till often contains isolated boulders.

Shallow groundwater can be found in the weathered soil perched on top of the unweathered glacial till. This groundwater is typically localized and varies with recent precipitation and the condition of the upgradient land relative to recharge through infiltration.

**2.3 Subsurface Soil Conditions:** Dense to very dense glacial till is exposed in the previous cuts made to the east of the house and in the excavation for the northeastern detached garage. The uppermost 4 to 5 feet of the steep slope, which is within the site boundaries, appears to consist of fill soil originally placed for yard and landscape areas around the house when the site was developed with the current home. We observed dense glacial till exposed in the lower 5 feet of the cut slope along the ditch to the west of the site.

**2.4 Groundwater Conditions:** During our site visits, which occurred during the fall of 2009 and winter of 2010, no indications of groundwater seepage were apparent on the slopes along the east and west sides of the site. The potential for upgradient recharge of shallow groundwater is very limited at this property, due to the topography of the old railroad right-of-way upslope to the east of the site.

**2.5 Subsurface Contamination:** Not Applicable to this project.

### 3.0 DISCUSSION AND CONCLUSIONS

**3.1 Slope Stability:** The glacial till soils that underlie the site, and which will support the planned construction are not susceptible to instability during static or seismic loading conditions. We conducted a slope stability analysis of the western slope using the WinStabl program. Based on the results of this analysis, the safety factor against a failure extending into the dense glacial till is in excess of 2.0 for static and 1.5 for seismic conditions. A copy of the topographic and geologic cross-section, and the critical failure surfaces for the static and seismic analyses are attached to this report.

**3.2 Seismic Considerations:** In accordance with Table 1613.5.2 of the 2006 International Building Code (IBC), the site soil profile within 100 feet of the ground surface is best represented by Site Class Type C (Very Dense Soil). The glacially-compressed soils that will support the foundations are not susceptible to seismic liquefaction. As noted in the USGS website, the mapped spectral acceleration value for a 0.2 second ( $S_s$ ) and 1.0 second period ( $S_1$ ) equals 1.44g and 0.49g, respectively. Seismic stability of the glacially-compressed soils is discussed in subsection 3.1 above.

**3.3 Site Work:** The only site work anticipated for this project involves excavation to reach adequate bearing soil, installation of subsurface drainage along the perimeter walls of the additions, and a small amount of backfilling of these walls. Recommendations for subsurface drainage and surface grading adjacent to the new foundation walls are presented in following sub-sections. We expect that the area between the existing house and the steep western slope will remain undisturbed. Appropriate temporary erosion control measures, as discussed below, will need to be implemented to prevent off-site impacts.

**3.4 Retaining Structures:** The only retaining walls anticipated for the new construction are the foundation walls for the northeastern addition. No stand-alone walls are expected.

**3.5 Rockeries:** New rockeries are not anticipated for the project.

**3.6 Foundation Support:** Conventional foundations can be used to support the additions and the new covered deck. All footings must be excavated down to dense, native soil.

#### 4.0 RECOMMENDATIONS

**4.1 Site Grading and Earthwork:** The amount of grading, including filling, expected for this project is negligible. All building and pavement areas should be stripped of surface vegetation, topsoil, organic soil, and other deleterious material. The stripped or removed materials should not be mixed with any materials to be used as structural fill, but they could be used in non-structural areas, such as landscape beds.

Structural fill is defined as any fill placed under foundations or slabs, or behind permanent foundation walls. All structural fill should be placed in horizontal lifts with a moisture content at, or near, the optimum moisture content. The optimum moisture content is that moisture content that results in the greatest compacted dry density. The moisture content of fill is very important and must be closely controlled during the filling and compaction process.

If grading activities take place during wet weather, or when the silty, on-site soil is wet, site preparation costs may be higher because of delays due to rain and the potential need to import granular fill. The on-site soil is generally silty and therefore moisture sensitive. Grading operations will be difficult during wet weather, or when the moisture content of this soil exceeds the optimum moisture content.

The moisture content of the silty, on-site soil must be at, or near, the optimum moisture content, as the soil cannot be consistently compacted to the required density when the moisture content is significantly greater than optimum. The moisture content of the on-site soil was generally above the estimated optimum moisture content at the time of our explorations. The on-site silty sand underlying the topsoil could be used as structural fill, if grading operations are conducted during hot, dry weather, when drying the wetter soil by aeration is possible. During excessively dry weather, however, it may be necessary to add water to achieve the optimum moisture content.

Structural fill that will be placed in wet weather should consist of a coarse, granular soil with a silt or clay content of no more than 5 percent. The percentage of particles passing the No. 200 sieve should be measured from that portion of soil passing the three-quarter-inch sieve.

**4.2 Temporary Shoring and Retaining Walls:** Temporary excavation shoring will not be needed for this project. We expect that temporary sloped cuts for the foundation excavations will be possible in the dense soils without the use of shoring.

Permanent foundation walls taller than approximately 2 feet that are backfilled on only one side should be designed to resist the lateral earth pressures imposed by the soil they retain.

The following recommended parameters are for walls that restrain level backfill:

PARAMETER	Value
Active Earth Pressure *	40 pcf
Passive Earth Pressure	300 pcf
Coefficient of Friction	0.45
Soil Unit Weight	130 pcf

Where: (i) pcf is pounds per cubic foot, and (ii) active and passive earth pressures are computed using the equivalent fluid pressures.

\* For a restrained wall that cannot deflect at least 0.002 times its height, a uniform lateral pressure equal to 10 psf times the height of the wall should be added to the above active equivalent fluid pressure.

The values given above are to be used to design only permanent foundation and retaining walls that are to be backfilled, such as conventional walls constructed of reinforced concrete or masonry. It is not appropriate to use the above earth pressures and soil unit weight to back-calculate soil strength parameters for design of other types of retaining walls, such as soldier pile, reinforced earth, modular or soil nail walls. We can assist with design of these types of walls, if desired. The passive pressure given is appropriate for the depth of level structural fill placed in front of a retaining or foundation wall only. The values for friction and passive resistance are ultimate values and do not include a safety factor. We recommend a safety factor of at least 1.5 for overturning and sliding, when using the above values to design the walls. Restrained wall soil parameters should be utilized for a distance of 1.5 times the wall height from corners or bends in the walls. This is intended to reduce the amount of cracking that can occur where a wall is restrained by a corner.

The design values given above do not include the effects of any hydrostatic pressures behind the walls and assume that no surcharges, such as those caused by slopes, vehicles, or adjacent foundations will be exerted on the walls. If these conditions exist, those pressures should be added to the above lateral soil pressures. Where sloping backfill is desired behind the walls, we will need to be given the wall dimensions and the slope of the backfill in order to provide the appropriate design earth pressures. Heavy construction equipment should not be operated behind retaining and foundation walls within a distance equal to the height of a wall, unless the walls are designed for the additional lateral pressures resulting from the equipment.

#### **Wall Pressures Due to Seismic Forces**

The surcharge wall loads that could be imposed by the design earthquake can be modeled by adding a uniform lateral pressure to the above-recommended active pressure. The recommended surcharge pressure is  $7H$  pounds per square foot (psf), where  $H$  is the design retention height of the wall. Using this increased pressure, the safety factor against sliding and overturning can be reduced to 1.2 for the seismic analysis.

### **Retaining Wall Backfill and Waterproofing**

Backfill placed behind retaining or foundation walls should be coarse, free-draining structural fill containing no organics. This backfill should contain no more than 5 percent silt or clay particles and have no gravel greater than 4 inches in diameter. The percentage of particles passing the No. 4 sieve should be between 25 and 70 percent. The on-site soils are silty, and are not free-draining. If these soils are dry enough to be adequately compacted, and are used as wall backfill, a minimum 12-inch width of free-draining gravel should be placed against the backfilled retaining walls. This would allow rapid downward movement of water to the footing drain system.

The purpose of these backfill requirements is to ensure that the design criteria for a retaining wall are not exceeded because of a build-up of hydrostatic pressure behind the wall. The top 12 to 18 inches of the backfill should consist of a compacted, relatively impermeable soil or topsoil, or the surface should be paved. The ground surface must also slope away from backfilled walls to reduce the potential for surface water to percolate into the backfill.

It is critical that the wall backfill be placed in lifts and be properly compacted, in order for the above-recommended design earth pressures to be appropriate. The wall design criteria assume that the backfill will be well-compacted in lifts no thicker than 12 inches. The compaction of backfill near the walls should be accomplished with hand-operated equipment to prevent the walls from being overloaded by the higher soil forces that occur during compaction.

The above recommendations are not intended to waterproof below-grade walls, or to prevent the formation of mold, mildew or fungi in interior spaces. Over time, the performance of subsurface drainage systems can degrade, subsurface groundwater flow patterns can change, and utilities can break or develop leaks. Therefore, waterproofing should be provided where future seepage through the walls is not acceptable. This typically includes limiting cold-joints and wall penetrations, and using bentonite panels or membranes on the outside of the walls. There are a variety of different waterproofing materials and systems, which should be installed by an experienced contractor familiar with the anticipated construction and subsurface conditions. Applying a thin coat of asphalt emulsion to the outside face of a wall is not considered waterproofing, and will only help to reduce moisture generated from water vapor or capillary action from seeping through the concrete. As with any project, adequate ventilation of basement and crawl space areas is important to prevent a build up of water vapor that is commonly transmitted through concrete walls from the surrounding soil, even when seepage is not present. This is appropriate even when waterproofing is applied to the outside of foundation and retaining walls. We recommend that you contact a specialty consultant if detailed recommendations or specifications related to waterproofing design, or minimizing the potential for infestations of mold and mildew are desired.

**4.3 Rockeries:** Not Applicable to expected scope of development.

**4.4 Reinforced Soil Structures:** Not Applicable to expected scope of development.

**4.5 Structure and Foundations:** All new foundations should bear on dense, native soils. We recommend that continuous and individual spread footings have minimum widths of 12 and 16 inches, respectively. Exterior footings should also be bottomed at least 18 inches below the

lowest adjacent finish ground surface for protection against frost and erosion. The local building codes should be reviewed to determine if different footing widths or embedment depths are required. Footing subgrades must be cleaned of loose or disturbed soil prior to pouring concrete. Depending upon site and equipment constraints, this may require removing the disturbed soil by hand.

An allowable bearing pressure of 2,000 pounds per square foot (psf) is appropriate for footings supported on competent native soil. A one-third increase in this design bearing pressure may be used when considering short-term wind or seismic loads. For the above design criteria, it is anticipated that the total post-construction settlement of footings founded on competent native soil will be less than one inch, with differential settlements on the order of one-quarter inch in a distance of 25 feet along a continuous footing with a uniform load.

Lateral loads due to wind or seismic forces may be resisted by friction between the foundation and the bearing soil, or by passive earth pressure acting on the vertical, embedded portions of the foundation. For the latter condition, the foundation must be either poured directly against relatively level, undisturbed soil or be surrounded by level structural fill. We recommend using the following ultimate values for the foundation's resistance to lateral loading:

PARAMETER	ULTIMATE VALUE
Coefficient of Friction	0.45
Passive Earth Pressure	300 pcf

Where: (i) pcf is pounds per cubic foot, and (ii) passive earth pressure is computed using the equivalent fluid density.

If the ground in front of a foundation is loose or sloping, the passive earth pressure given above will not be appropriate. We recommend maintaining a safety factor of at least 1.5 for the foundation's resistance to lateral loading, when using the above ultimate values.

**4.6 Floors:** Where slab-on-grade floors are used, the subgrade soil must be in a firm, non-yielding condition at the time of slab construction or underslab fill placement. Any soft areas encountered should be excavated and replaced with select, imported structural fill.

Even where the exposed soils appear dry, water vapor will tend to naturally migrate upward through the soil to the new constructed space above it. This can affect moisture-sensitive flooring, cause imperfections or damage to the slab, or simply allow excessive water vapor into the space above the slab. All interior slabs-on-grade should be underlain by a capillary break or drainage layer consisting of a minimum 4-inch thickness of gravel or crushed rock that has a fines content (percent passing the No. 200 sieve) of less than 3 percent and a sand content (percent passing the No. 4 sieve) of no more than 10 percent.

As noted by the American Concrete Institute (ACI) in the *Guides for Concrete Floor and Slab Structures*, proper moisture protection is desirable immediately below any on-grade slab that will be covered by tile, wood, carpet, impermeable floor coverings, or any moisture-sensitive equipment or products. ACI also notes that vapor *retarders*, such as 6-mil plastic sheeting, have been used in the past, but are now recommending a minimum 10-mil thickness. A vapor retarder is defined as a material with a permeance of less than 0.3 perms, as determined by

ASTM E 96. It is possible that concrete admixtures may meet this specification, although the manufacturers of the admixtures should be consulted. Where vapor retarders are used under slabs, their edges should overlap by at least 6 inches and be sealed with adhesive tape. The sheeting should extend to the foundation walls for maximum vapor protection. If no potential for vapor passage through the slab is desired, a vapor *barrier* should be used. A vapor barrier, as defined by ACI, is a product with a water transmission rate of 0.01 perms when tested in accordance with ASTM E 96. Reinforced membranes having sealed overlaps can meet this requirement.

**4.7 Pavements:** Not Applicable to expected scope of development.

**4.8 Utilities:** Not Applicable to expected scope of development.

**4.9 Drainage:** Refer to sub-section 4.6 for water and moisture control beneath floor slabs. A vapor retarder/barrier similar to that discussed in sub-section 4.6 should be included in any crawl space area. An outlet drain and a layer of at least 4 inches of free-draining gravel should also be provided below the vapor retarder/barrier in any crawl space area to prevent an accumulation of subsurface water that may bypass the perimeter foundation drains.

Foundation drains should be used where (1) crawl spaces or basements will be below a structure, (2) a slab is below the outside grade, or (3) the outside grade does not slope downward from a building. Drains should also be placed at the base of all earth-retaining walls. These drains should be surrounded by at least 6 inches of 1-inch-minus, washed rock and then wrapped in non-woven, geotextile filter fabric (Mirafi 140N, Supac 4NP, or similar material). At its highest point, a perforated pipe invert should be at least 6 inches below the bottom of a slab floor or the level of a crawl space, and it should be sloped for drainage. All roof and surface water drains must be kept separate from the foundation drain system. A typical drain detail is attached to this report. For the best long-term performance, perforated PVC pipe is recommended for all subsurface drains.

Final site grading in areas adjacent to a foundation wall should slope away at least 2 percent, except where the area is paved. Surface drains should be provided where necessary to prevent ponding of water behind foundation or retaining walls.

**4.10 Hazards and Mitigation:** The proposed new construction will be located no closer than 15 feet to the crest of the steep western slope. The area that will be disturbed by the northwestern addition and the portion of the new covered deck closest to the western slope is currently covered by asphalt pavement. The footings for the new construction are to bear on dense glacial till. The glacial till soils that underlie the property are relatively incompressible and have a very high internal strength. In order to prevent the project from increasing the landslide potential on the western slope, we recommend the following:

- Leave the steep slope, including its existing vegetated cover, undisturbed.
- Place no new fill in the area between the house and the steep slope. If desired, some of the existing fill could be removed in this area, provided the excavation stops at the face of the steep slope. Soil resulting from excavation should either be used for backfill on the east side of the house, or be hauled off the site.
- Excavate all new footings, including those for the deck down to dense, native soil.

- Avoid discharging concentrated water from impervious areas toward the slope.

The steep slope to the west of the proposed work area appears to have been created by past grading, but it is not excessively tall. Considering the competent nature of the underlying soils that will support the additions and new deck, and the fact that the new construction will not encroach closer to the steep slope than the existing house, we support a modification to Bellevue Land Use Code (LUC) 20.25H.120, which requires a 50-foot buffer from steep slopes. The planned construction of the additions and the northern deck will not adversely affect the stability of the steep slope, nor would future soil movement on the slope affect the new construction, provided the recommendations of this report are followed. The buffer area has already been degraded by past construction and grading for the house, and paving of the driveway and parking areas. The planned construction will not cause additional degradation of the buffer area, nor will it adversely impact stability of the slope. In fact, the planned construction may improve slope stability slightly, as the runoff from the additions and covered deck will be discharged off the site away from the steep slope.

Beyond the above recommended measures, no mitigation, such as planting additional vegetation, is necessary for the project to encroach into the minimum 50-foot buffer area. Considering the planned scope of the development, it is our professional opinion that a minimum 10-foot buffer is acceptable.

The 1990 King County *Sensitive Areas Map Folio* shows the steep manmade slope west of the site to be mapped as an erosion hazard area. This is due to the inclination of the slope. The slope is covered with well-established vegetation and does not pose an erosion hazard in its current condition. The proposed project will not disturb the slope, or result in grading close to the slope that could increase the potential for erosion. We expect that only minimal erosion control measures will be needed for this project, due to the very limited amount of ground disturbance expected. It is likely that a silt fence will not be needed, and would not be effective for this project. The foundation excavations should be covered with plastic or crushed rock during wet weather to prevent silty runoff. Any temporary stockpiles should be covered with plastic in wet conditions. Trucks and other equipment should be kept on the existing pavement or gravel-covered areas to prevent tracking soil or mud off the site. Excavations should be backfilled as quickly and possible, and the rough-graded ground surface covered with mulch, straw, plastic or another appropriate erosion control element until permanent landscaping is complete.

### **LIMITATIONS**

The conclusions and recommendations contained in this report are based on site conditions as they existed at the time of our site visit. If the subsurface conditions encountered during construction are significantly different from those anticipated, we should be advised at once so that we can review these conditions and reconsider our recommendations where necessary. Unanticipated soil conditions are commonly encountered on construction sites. Such unexpected conditions frequently require making additional expenditures to attain a properly constructed project.

This report has been prepared for the exclusive use of Craig Schaff and his representatives for specific application to this project and site. Our recommendations and conclusions are based on the site materials observed and on previous experience with sites that have similar observed conditions. The conclusions and recommendations are professional opinions derived in accordance with current standards of practice within the limited scope of our services. No warranty is expressed or implied.

If you have any questions, or if we may be of further service, please do not hesitate to contact us.

Respectfully submitted,

GEOTECH CONSULTANTS, INC.




Marc R. McGinnis, P.E.  
Principal

cc: **Greg Jones**  
*via email*  
**Dona Architecture**  
*via email*

Attachments-Vicinity Map, Site Plan, Footing Drain Detail, Slope Stability Analyses

MRM: jyb



(Source: Thomas Brothers Street Guide and Directory)


NORTH




**VICINITY MAP**  
 4326 Lk. Wash. Blvd. N.E.  
 Bellevue, Washington

<b>Job No:</b> 09310	<b>Date:</b> April 2010	<b>Plate:</b> Not To Scale
-------------------------	----------------------------	-------------------------------

157  
 158  
 159  
 160  
 161  
 162  
 163  
 164  
 165  
 166  
 167  
 168  
 169  
 170  
 171  
 172  
 173  
 174  
 175  
 176  
 177  
 178  
 179  
 180  
 181  
 182  
 183  
 184  
 185  
 186  
 187  
 188  
 189  
 190  
 191  
 192  
 193  
 194  
 195  
 196  
 197  
 198  
 199  
 200  
 201  
 202  
 203  
 204  
 205  
 206  
 207  
 208  
 209  
 210  
 211  
 212  
 213  
 214  
 215  
 216  
 217  
 218  
 219  
 220  
 221  
 222  
 223  
 224  
 225  
 226  
 227  
 228  
 229  
 230  
 231  
 232  
 233  
 234  
 235  
 236  
 237  
 238  
 239  
 240  
 241  
 242  
 243  
 244  
 245  
 246  
 247  
 248  
 249  
 250  
 251  
 252  
 253  
 254  
 255  
 256  
 257  
 258  
 259  
 260  
 261  
 262  
 263  
 264  
 265  
 266  
 267  
 268  
 269  
 270  
 271  
 272  
 273  
 274  
 275  
 276  
 277  
 278  
 279  
 280  
 281  
 282  
 283  
 284  
 285  
 286  
 287  
 288  
 289  
 290  
 291  
 292  
 293  
 294  
 295  
 296  
 297  
 298  
 299  
 300  
 301  
 302  
 303  
 304  
 305  
 306  
 307  
 308  
 309  
 310  
 311  
 312  
 313  
 314  
 315  
 316  
 317  
 318  
 319  
 320  
 321  
 322  
 323  
 324  
 325  
 326  
 327  
 328  
 329  
 330  
 331  
 332  
 333  
 334  
 335  
 336  
 337  
 338  
 339  
 340  
 341  
 342  
 343  
 344  
 345  
 346  
 347  
 348  
 349  
 350  
 351  
 352  
 353  
 354  
 355  
 356  
 357  
 358  
 359  
 360  
 361  
 362  
 363  
 364  
 365  
 366  
 367  
 368  
 369  
 370  
 371  
 372  
 373  
 374  
 375  
 376  
 377  
 378  
 379  
 380  
 381  
 382  
 383  
 384  
 385  
 386  
 387  
 388  
 389  
 390  
 391  
 392  
 393  
 394  
 395  
 396  
 397  
 398  
 399  
 400  
 401  
 402  
 403  
 404  
 405  
 406  
 407  
 408  
 409  
 410  
 411  
 412  
 413  
 414  
 415  
 416  
 417  
 418  
 419  
 420  
 421  
 422  
 423  
 424  
 425  
 426  
 427  
 428  
 429  
 430  
 431  
 432  
 433  
 434  
 435  
 436  
 437  
 438  
 439  
 440  
 441  
 442  
 443  
 444  
 445  
 446  
 447  
 448  
 449  
 450  
 451  
 452  
 453  
 454  
 455  
 456  
 457  
 458  
 459  
 460  
 461  
 462  
 463  
 464  
 465  
 466  
 467  
 468  
 469  
 470  
 471  
 472  
 473  
 474  
 475  
 476  
 477  
 478  
 479  
 480  
 481  
 482  
 483  
 484  
 485  
 486  
 487  
 488  
 489  
 490  
 491  
 492  
 493  
 494  
 495  
 496  
 497  
 498  
 499  
 500  
 501  
 502  
 503  
 504  
 505  
 506  
 507  
 508  
 509  
 510  
 511  
 512  
 513  
 514  
 515  
 516  
 517  
 518  
 519  
 520  
 521  
 522  
 523  
 524  
 525  
 526  
 527  
 528  
 529  
 530  
 531  
 532  
 533  
 534  
 535  
 536  
 537  
 538  
 539  
 540  
 541  
 542  
 543  
 544  
 545  
 546  
 547  
 548  
 549  
 550  
 551  
 552  
 553  
 554  
 555  
 556  
 557  
 558  
 559  
 560  
 561  
 562  
 563  
 564  
 565  
 566  
 567  
 568  
 569  
 570  
 571  
 572  
 573  
 574  
 575  
 576  
 577  
 578  
 579  
 580  
 581  
 582  
 583  
 584  
 585  
 586  
 587  
 588  
 589  
 590  
 591  
 592  
 593  
 594  
 595  
 596  
 597  
 598  
 599  
 600  
 601  
 602  
 603  
 604  
 605  
 606  
 607  
 608  
 609  
 610  
 611  
 612  
 613  
 614  
 615  
 616  
 617  
 618  
 619  
 620  
 621  
 622  
 623  
 624  
 625  
 626  
 627  
 628  
 629  
 630  
 631  
 632  
 633  
 634  
 635  
 636  
 637  
 638  
 639  
 640  
 641  
 642  
 643  
 644  
 645  
 646  
 647  
 648  
 649  
 650  
 651  
 652  
 653  
 654  
 655  
 656  
 657  
 658  
 659  
 660  
 661  
 662  
 663  
 664  
 665  
 666  
 667  
 668  
 669  
 670  
 671  
 672  
 673  
 674  
 675  
 676  
 677  
 678  
 679  
 680  
 681  
 682  
 683  
 684  
 685  
 686  
 687  
 688  
 689  
 690  
 691  
 692  
 693  
 694  
 695  
 696  
 697  
 698  
 699  
 700  
 701  
 702  
 703  
 704  
 705  
 706  
 707  
 708  
 709  
 710  
 711  
 712  
 713  
 714  
 715  
 716  
 717  
 718  
 719  
 720  
 721  
 722  
 723  
 724  
 725  
 726  
 727  
 728  
 729  
 730  
 731  
 732  
 733  
 734  
 735  
 736  
 737  
 738  
 739  
 740  
 741  
 742  
 743  
 744  
 745  
 746  
 747  
 748  
 749  
 750  
 751  
 752  
 753  
 754  
 755  
 756  
 757  
 758  
 759  
 760  
 761  
 762  
 763  
 764  
 765  
 766  
 767  
 768  
 769  
 770  
 771  
 772  
 773  
 774  
 775  
 776  
 777  
 778  
 779  
 780  
 781  
 782  
 783  
 784  
 785  
 786  
 787  
 788  
 789  
 790  
 791  
 792  
 793  
 794  
 795  
 796  
 797  
 798  
 799  
 800  
 801  
 802  
 803  
 804  
 805  
 806  
 807  
 808  
 809  
 810  
 811  
 812  
 813  
 814  
 815  
 816  
 817  
 818  
 819  
 820  
 821  
 822  
 823  
 824  
 825  
 826  
 827  
 828  
 829  
 830  
 831  
 832  
 833  
 834  
 835  
 836  
 837  
 838  
 839  
 840  
 841  
 842  
 843  
 844  
 845  
 846  
 847  
 848  
 849  
 850  
 851  
 852  
 853  
 854  
 855  
 856  
 857  
 858  
 859  
 860  
 861  
 862  
 863  
 864  
 865  
 866  
 867  
 868  
 869  
 870  
 871  
 872  
 873  
 874  
 875  
 876  
 877  
 878  
 879  
 880  
 881  
 882  
 883  
 884  
 885  
 886  
 887  
 888  
 889  
 890  
 891  
 892  
 893  
 894  
 895  
 896  
 897  
 898  
 899  
 900  
 901  
 902  
 903  
 904  
 905  
 906  
 907  
 908  
 909  
 910  
 911  
 912  
 913  
 914  
 915  
 916  
 917  
 918  
 919  
 920  
 921  
 922  
 923  
 924  
 925  
 926  
 927  
 928  
 929  
 930  
 931  
 932  
 933  
 934  
 935  
 936  
 937  
 938  
 939  
 940  
 941  
 942  
 943  
 944  
 945  
 946  
 947  
 948  
 949  
 950  
 951  
 952  
 953  
 954  
 955  
 956  
 957  
 958  
 959  
 960  
 961  
 962  
 963  
 964  
 965  
 966  
 967  
 968  
 969  
 970  
 971  
 972  
 973  
 974  
 975  
 976  
 977  
 978  
 979  
 980  
 981  
 982  
 983  
 984  
 985  
 986  
 987  
 988  
 989  
 990  
 991  
 992  
 993  
 994  
 995  
 996  
 997  
 998  
 999  
 1000




-  CONCRETE PAVING
-  GRAVEL SURFACE
-  EXISTING RETAINING WALL
-  40%+ SLOPE (HEIGHT DIFFERENCE GREATER THAN 10 FEET, AREA SHOWN)



NORTH

**SITE PLAN**  
SCALE: 1" = 10'-0"

A11  
 A21  
 A31  
 A32



**NOTES:**

- (1) In crawl spaces, provide an outlet drain to prevent buildup of water that bypasses the perimeter footing drains.
- (2) Refer to report text for additional drainage and waterproofing considerations.



<b>TYPICAL FOOTING DRAIN</b>			
4326 Lk. Wash. Blvd. N.E. Bellevue, Washington			
<i>Job</i> 09310	<i>Date:</i> April 2010	<i>Scale:</i> Not to Scale	<i>Plate:</i>

Profile.out  
\*\* PCSTABL6 \*\*

by  
Purdue University

modified by  
Peter J. Bosscher  
University of Wisconsin-Madison

--Slope Stability Analysis--  
Simplified Janbu, Simplified Bishop  
or Spencer's Method of Slices

PROBLEM DESCRIPTION

BOUNDARY COORDINATES

5 Top Boundaries  
6 Total Boundaries

Boundary No.	X-Left (ft)	Y-Left (ft)	X-Right (ft)	Y-Right (ft)	Soil Type Below Bnd
1	0.00	10.00	10.00	10.00	2
2	10.00	10.00	17.00	15.00	2
3	17.00	15.00	40.00	30.00	1
4	40.00	30.00	55.00	30.00	1
5	55.00	30.00	75.00	30.00	2
6	17.00	15.00	55.00	30.00	2

ISOTROPIC SOIL PARAMETERS

2 Type(s) of soil

Soil Type No.	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Pore Pressure Param.	Pressure Constant (psf)	Piez. Surface No.
1	125.0	135.0	0.0	28.0	0.00	0.0	0
2	140.0	150.0	0.0	45.0	0.00	0.0	0

A Critical Failure Surface Searching Method, Using A Random  
Page 1

Profile.out  
Technique For Generating Circular Surfaces, Has Been Specified.

40 Trial Surfaces Have Been Generated.

20 Surfaces Initiate From Each Of 2 Points Equally Spaced  
Along The Ground Surface Between X = 10.00 ft.  
and X = 20.00 ft.

Each Surface Terminates Between X = 55.00 ft.  
and X = 65.00 ft.

Unless Further Limitations Were Imposed, The Minimum Elevation  
At Which A Surface Extends Is Y = 10.00 ft.

5.00 ft. Line Segments Define Each Trial Failure Surface.

Following Are Displayed The Ten Most Critical Of The Trial  
Failure Surfaces Examined. They Are Ordered - Most Critical  
First.

\* \* safety Factors Are Calculated By The Modified Bishop Method \* \*

Failure Surface Specified By 11 Coordinate Points


Point No.	X-Surf (ft)	Y-Surf (ft)
1	10.00	10.00
2	14.59	11.99
3	19.18	13.98
4	23.76	15.98
5	28.34	17.98
6	32.91	20.00
7	37.49	22.02
8	42.06	24.05
9	46.62	26.09
10	51.19	28.13
11	55.35	30.00

Circle Center At X = \*\*\*\*\* ; Y = 2866.3 and Radius, 3110.9

\*\*\* 2.263 \*\*\*

Failure Surface Specified By 12 Coordinate Points


Point No.	X-Surf (ft)	Y-Surf (ft)
--------------	----------------	----------------



Safety Factors

2.26
2.28
2.29
2.33
2.39
2.39
2.46
2.50
2.51
2.52

Static



Safety Factors

1.58
1.59
1.60
1.63
1.67
1.70
1.70
1.73
1.73
1.77

Earthquake